

SURVEY &
REMONUMENTATION

FEB 16 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>18</u> R <u>10W</u>	<u>E-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
22 Oct 1998

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Matthew McClung in a field survey on 6-24, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor John Hodgson on 10 June 1838. Set wood post 80.00 chains from South

Beech 8" N76E 22 lks.
Beech 8" S65W 35 lks.

Act 74, Liber 12, page 69 Fd 1" Pipe
N40E 47.37' TP
N10W 99.69' 26" TW Cherry
N50W 73.34' 12" Red Pine

Act 132, Liber 352, Page 242
10" Pine NW 68.70'
P.P. ENE 96.51'
Centerline Well Head SW 131.05'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Iron and cap No. 24624 in monument Box. Corner is in centerline of Roads North and South and East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Corner E-7. Corner is the found 1/2" iron and cap No. 24624 in monument box.

P. Pole S60E 107.05 feet.
P. Pole S70W 153.75 feet.
R Pine N40W 67.5 feet.
8" R. Pine N60E 105.55 feet (Nail)



Signed by *Matthew McClung*
Surveyor's Michigan License No. 13037

Date 23 Nov. 98

98 NOV 23 AM 10:38

Nancy Crawford

SUBJECT
REMONUMENTATION

FEB 16 1899

SECTION

Act 132. Liber 312 Page 1
Fd Iron
Nail 8" Pine N45W 68.2'
Nail P. Pole N50E 47.0'
NE Corner Gas Pump House
S55W 127.5'

Act 132 Liber 433, Page 62
Fd RR Spike in Mon. Box
N45W Nail in R. Pine 68.25'
N70E Nail in P. Pole 96.40'
S45E Rd. Sign 56.05'

Act 132, Liber 413 page 693
Fd RR Spike
N45W 68.25' to Nail in 10" R. Pine
N70E 96.40' to Nail in P. Pole
S45E 56.05' to Road Sign

Act 132, Liber 422 Page 571
Fd 1" Pipe in Monument Box
Well head # 45 Az 237 131.00'
Fd. Nail W/RLS Tag # 14091 in West Side of 12" R. Pine az 324 68.69'
recorded as N50W 73.34
FD RR Spike in East side of 26" Twin Cherry Az 350 99.69'