

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>18N</u> R <u>10W</u> | <u>K-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
29 Nov. 1994

Register of Deeds Stamp & File Number

~~Matthew McClung~~, in a field survey on November 28, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
The original corner was set by deputy surveyor John Hodgson on 10 June 1838. Set wood post 80.00 chains from South.
Beech 9" S45E 42 lks.
Beech 7" N19E 14 lks.
There are 2 LCRC recordings, Lib. 1, page 381 and Lib 1, Page 394, by McClung.
There are 5 act 132 recordings.

B. Description of corner evidence found and/or method applied in restoring or re-establishing surface. Removed Found concrete monument in road centerline replaced with Osceola County Monument, in same position, 7" below road surface.

OSCEOLA COUNTY
REGISTER OF DEEDS

94 DEC -7 PM 2:51

Nancy Crawford



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner K-5. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
Plat Monument West 33.0 feet, adjacent to down fence post. O.B.P.
Concrete Monument East 33.0 feet. O.B.P.
Power pole S59e 30.53 feet. O.B.P.
4" R. Oak N75W 52.86 feet. O.B.T.

Signed by *Matthew McClung*

Date November 28, 1994

Surveyor's Michigan License No. 13037

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983