

LAUSING

0300066

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>19</u> N. <u>9</u> E. <u>W.</u>		F-13 K-11 M-10
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S. _____ R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 10-13-72 19 , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- F-13 A. Temple 1892 set monument and marked: Pine stp 24 N45W 7; Pine stp 16 N19E 17.
- K-11 A. Temple 1892 found stake and USBTs. Set monument and marked: Pine stp 40" S68E 77;
Pine stp 17" N 1E 20
- M-10 A. Temple 1892 found USBT. Set Monument and marked: Pine stp 40 N53W 59
Black Oak 28 N85W 43

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-13 Found Temple monument and remains of one of his witnesses.
- K-11 Found Temple monument and remains of his witnesses.
- M-10 Found Temple monument and remains of his witness NE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13	K-11	M-10
Left 1/2" bar in 3" vit tile in place. Added Cedar Guard Post	Added Squared Cedar Post & Tag. 1/2" rod in 3' tile mon. in place.	Added squared Cedar Post w/tag. Left 1/2" rod in vit. tile in place
B. Oak 20" N42E 83.0'	17" Cherry N17E 16.7'	25" S. Maple S67W 32.8'
B. Oak 22" N66W 39.1'	10" W. Oak clpN20W 75.2'	12" R. Maple S29E 35.3'
	9" Cherry S60E 58.7'	Ctr of small swp hole w/ S35W 127±10'
	On steep SW'ly slope	water & cattails

SIGNED BY Kenneth J. Ostling DATE 11/11

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____