

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 19 N. XX R. 9 XX W.	G-12 H-12
2. PROPERTY CONTROLLING IN SECTION _____	Sec 34, T. 19 N. XX R. 9 XX W.	Code 8
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11-9 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- G-12 Set corner by proportionate measurement between section corners. Unable to locate Temple corner or identify his witness. Falls about 100' West of meandering N-S fence.
- H-12 Set corner at calculated intersection of true 1/4 lines.
- Code 8 Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12	H-12	Code 8
Set Std. Dept. Mon.	Set 1"x36" Pipe	Set 1"x36" Pipe
11" R. Oak N53W 9.8'	9" Maple N20E 24.5'	14" R. Oak N68E 54.9.
11" R. Oak N 32E 16.9'	9" R. Oak S56E 17.5'	17" Cherry S26E 24.1
22" Oak S43W 17.9'	(.11 R. Oak) N75W 4.0'	16" R. Oak S34W 40.7
	in clump of two)	

SIGNED BY Kenneth J. Ostling DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____