

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. <u>19</u> N. S. R. <u>9</u> E. W.		M-11 M-12 M-13
2. PROPERTY CONTROLLING IN SECTION_____ T. _____ N. S., R. _____ E. W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION_____ T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram -- over) were, in a field survey on 10-11-72 19___, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19___, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-11 A. Temple 1892 - Found original corner tree, marked: Pine stp 28 S 5W 23
Pine Stp 30 N73E 20
- M-12 A. Temple 1892, found stake and local witness, set tile monument.
- M-13 A. Temple 1892 - Set tile monument and marked witnesses: Pine stp 15 S40E 34
Pine stp 18 N70E 7

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-11 Found Temple's monument and witnesses in place but badly rotted.
- M-12 Found Temple monument and witness remains.
- M-13 Found Temple monument and witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11	M-12	M-13
1/2"x4' iron rod in 3" vit tile, in place. Added squared Cedar Post & Tag	Left iron in tile mon in place. Added Squared Cedar Post & Tag	1/2" Iron bar in 3" Vit tile, in place. Added Squared Cedar Post & Tag
9" R. Oak N 5E 16.7'	20" Oak N75W 16.5'	27" B. Oak N34W 65.4'
11" R. Maple S27W 25.8'	21" Oak S 3W 17.3'	15" W. Oak 2-clump N23E 48.8'
20" Oak S26E 37.9'	17" Oak S34E 46.7'	8" R. Maple 4-clp S50E 19.9'
		Ctr line old R.R. grade SE 15' course NE-SW

SIGNED BY Kenneth J. Ostling DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

