

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF	LOCATED IN-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 <sup>N.</sup> <del>X.</del> R. 9 <sup>X.</sup> <del>W.</del>	C-9; C-10
2. PROPERTY CONTROLLING IN SECTION	29 T. 19 <sup>N.</sup> <del>X.</del> R. 9 <sup>X.</sup> <del>W.</del>	3
3. MISCELLANEOUS PROPERTY IN SECTION	T. <sup>N.</sup> <del>X.</del> R. <sup>E.</sup> <del>W.</del>	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER


I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Aug. 23, 19 79, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- C-9 Found old 4" Conc. Monument (Sq.) with 1/2 inch rod (in swamp) in line with Ctr. of over-grown road bed to south and west. Fits plat of "McCoy Acres".
  - C-10 Found 3" Brass Cap Monument by McClung (1957) at position of recovered iron.
  - 3 Found 3/4 inch pipe in Approx. Ctr. of N-S Bit. surface County Road. Corner fits "Plat of Wahstead Acres".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	3	C-10	C-9
Fd 3/4" pipe, flush.		Fd. 3" Brass Cap Mon., flush.	Fd 4" Sq. Conc. Monument
5" Elm S70E 37.46		27" Basswood N85W 43.90	Fd Conc Mon Due E 49.9'
Fd Conc Mon Due E 33.0		Ctr N-S 20' B. rd. Due W 0.8'	4" W. Birch S75W 85.78
Ctr N-S 20' Bit. Road Due E 0.7'			8" Tamarack S55W 59.27
Ctr platted St E'y Due S 29'			



SIGNED BY Carl F. Roser DATE 11/06/79

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)  
 ROSE LAKE TOWNSHIP  
 OSCEOLA COUNTY