

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
OSCEOLA  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>9W</u>	<u>K-8</u>
	T _____ R _____	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL F. ROSER, in a field survey on 04/18, 19 84, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

<u>K-8</u>	<u>K-9</u>
------------	------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>K-8</u> FB. 4" DIA. BRASS CAPPED P.A.S. MONUMENT BY G.A. SHANKO WHO FB. CO. SURVEYOR A.O. TEMPLE'S (1892) IR. IN TILE. TEMPLE HAD BOTH U.S.B.T.'S. FRANK MCCLUNG HAD THIS COR. IN 1918 & TOOK TWO NOTS OF WHICH SHANKO FB IN 1953. OLD FN'S E-W-N IS 99'-N & 4' (±3')-N. FN NORTHERLY IS 8-N IN TREES..	<u>K-9</u> FB. OLD 1/2" ROD IN 3" TILE IN SMALL PILE OF STONES. THIS IS CO. SURVEYOR A. O. TEMPLE'S COR. (1892) WHO HAD U.S.B.T. HERE. FB. REMAINS OF ONE TEMPLE N.B.T. STUMP.
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>K-8</u> FB PAB MON & 3" TILE 8" ASH.. N35 E 25.1' 32" ELM STP IN CTR 17" DIA STONE PILE S70°E 40' 3" R.OAK S30°W 7.8' POINT ON TOP 3"14" STONE N50°W 19.7' OLD E-W FN REMAINS NORTH 4' (±3')	<u>K-9</u> FB 1/2" IRON ROD IN 3" TILE; ADDED CED POST W/LOC. TAG 6" R.OAK N20°W 41.9' 11" TW. SUB. MAPLE S50°E 7.7' 14" R.OAK (CLP 3) S75°W 11.4' OLD E-W FN REMAINS DUE S 30' (±2')
--	--

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Carl F. Roser 02-05-91 Date \_\_\_\_\_  
 Surveyor's Michigan License No. 12028

