

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OSCEOLA

(County)

Located In:

Corner Code ~~≠~~

- | | | |
|---------------------------------------|-----------------------------|--------------------|
| 1. Public Land Survey | T <u>19N</u> R <u>9W</u> | <u>K-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>24</u> T _____ R _____ | <u>5</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S <u>24</u> T _____ R _____ | <u>MUSNC 959.5</u> |
| | S _____ T _____ R _____ | <u>E OF L-7</u> |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, CARL F. ROSER, in a field survey on 04/18, 19 84, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


<u>K-7</u>	<u>5</u>	<u>MUSNC</u>
------------	----------	--------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>K-7</u> FD OSCEOLA CO MON AS SET BY NATT MCCLUNG AT FD TILE & IR; SAID TILE & IR BY CO. SURVEYOR A. D. TEMPLE (1892). COR IS IN APPROX. CTR OF GRAVEL RD INTER. E-W-N.	<u>5</u> ACCEPTED B. SHADKO (1953) BRASS CAPPED MON FOR NW COR. SW1/4-NE1/4, SEC. 24.	<u>MUSNC</u> FD. SHADKO BRASS CAPPED P.A.S. MONUMENT ON N. LINE OF SEC. 24 (N89°27'43"E, 959.48 FROM N 1/4 COR OF S-24) & WEST SIDE OF SUNRISE LAKE. U.S. HAD 962.3'.
---	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>K-7</u> FD OSCEOLA CO MON. P. POLE N50°W 93.08' 16" R. PINE N20°W 109.83' P. POLE S E 48.32' SET CED POST W/LOC. TAG. DUE S 33'	<u>5</u> FD PAS MON; ADDED CED. POST W/LOC TAG. 12" SUB. MAPLE IN CLUMP 3 N15°E 14.1' 11" SUB. MAPLE IN CLUMP 2 N40°E 31.3' 16" TN R. OAK S33°E 17.9' FD 3/4" PIPE N30°W 7.3'	<u>MUSNC</u> FD PAS MON; ADDED CED. POST 16" R. OAK N15°W 19.03' 3" R. OAK S70°W 24.47' 13" MAPLE N80°W 37.59' WLY EDGE SUM- RISE LK. DUE E 36' WLY EDGE SUM- RISE LK. DUE S 24'
--	---	--



Signed by Carl F. Roser 02-05-91 Date _____
 Surveyor's Michigan License No. 12028