

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
		J-11 K-12 J-13 K-13
1. PUBLIC LAND SURVEY _____	T. <u>19</u> ^{N.} S. R. <u>9</u> ^{XX} W.	
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 10-10 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

J-11 A. Temple fd U.S. corner tree "dead standing" 1892 - Marked: Pine stub 36 S 5W 22 Pine stump 20 N24W 25	J-13 A. Temple 1892, Fd USBTs and set tile Mon. marked: Pine stp 36 N82E 40 Pine stp 36 N2½W 40	K-13 A. Temple, 1892 Fd USBT stp and set tile mon. marked: Pine stp 28" N25W 37 Pine stp 28 N52E 49
K-12 A. Temple 1892, Fd USBT Set tile mon and marked: Pine stub 20 N58E 11 Pine stp 20 N 9E 30		

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J-11) Fd Temple's Mon and remains of witness stumps.
 J-13) "
 K-12) "
 K-13 Fd Temple's monument and witnesses, and U.S.B.T. stump remains in place.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11: Left 1/2 bar in 3" tile in place. Added Ced.Gd Post & Tag 12" R. Maple N20W 47.9' 6" R. Maple S25E 28.3' 13" R. Oak S40W 9.2'	J-13: Left 1/2 bar in 3" tile in place. Added Ced.Gd Post & Tag 16" Oak N75W 80.8' 14" Maple S53W 93.8' E-W fn remains Due S 33'±3'	K-13: Left 1/2" bar in 3" tile, in place. Added Ced. Gd Post & Tag 18" W. Oak N63W 81.0' 12" R. Oak 2-clmp N25E 56.1' E-W Fn remains Due S 35±4
---	---	---

K-12: Left 1/2" bar in 3" tile in place, added Ced.Gd.Post
 11" R.Oak 2-clmp N20W 14.8'
 10" R. Oak S85E 12.4'

SIGNED BY Kenneth J. Ostling DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____