

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>19</u> N. <u>9</u> E. <u>W.</u> S. R. _____	I-11 I-12 I-13
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. R. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. R. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 10-10 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- I-11 A. Temple 1892 - Found U.S.B.T.s and set monument. Marked: Stp 30" N20E 47
Stp 19" S68E 33
 - I-13 A. Temple 1892 set corner from restored location of U.S. closing corner and marked: Pine stp 18 S82E 15
Pine stp 20 N34E 32

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- I-11 Found Temple's monument and remains of his witnesses and probable U.S.B.T. stump.
 - I-12 Found Temple's 1892 monument and remains of one witness.
 - I-13 Found Temple's tile mon and remains of his witnesses. Closing corner would be 53 links West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	I-11	I-12	I-13
Left 1/2" bar in 3" vit tile in place	Left 1/2" bar in 3" vit in place. Added Cedar guard post	Left 1/2" bar in 3" Vit rile in place. Added Cedar Guard Post	
Maple 10" S44E 13.3'	Maple 11" S07E 34.9'	24" W. Pine S75E 75.1'	
Maple 9" in clump of 4 S07W 18.5'	Maple 12" N45E 31.1'	13" Cherry N11W 15.6'	
Oak 21" N70W 47.6'	Cherry 11" N52W 24.4'	3" W. Pine N26E 40.7'	
E-W Fence North 246'		Ctr. Sand Rd Due W 21'	

SIGNED BY Kenneth J. Ostling DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068
 FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____
 APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

