

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola Located In: Corner Code #
(County)

1. Public Land Survey T___ R___
 T___ R___

2. Property Controlling S 34 T 19NR 9W 15
 in Section S___ T___ R___

3. Miscellaneous S___ T___ R___
 Property in Sec. S___ T___ R___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on July 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

15 - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

15 - W 1/16 Corner on S. line Sec. 34, T19N, R9W.
 Set 2" Alum. Cap on 5/8" x 34" rebar per standard BLM Procedure.
 Center of N-S Sand Rd. is 357' ± E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

15 - 2" A.C. on 5/8" x 34" Rebar.
 Built Ring of Stone.
 Set Blue Carsonite Post 1' SW
 East 341.75 to 2" A.C. on Twp. Line
 N69°W 25.95' to N&T in N. Side 5" R. Pine.
 N25°W 31.24' to N&T in E. Side 6" R. Pine.
 S3°W 75.62' to N&T in W. Side 8" R. Pine.
 S44°E 104.91' to N&T in NE Side 7" R. Pine.



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 12/9/1998