

NOV 16 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

| | | |
|------------------------------------|-------------|---------------|
| <u>Osceola</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 19N R 9W | H-13 |
| 2. Property Controlling in Section | T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| | S T R | |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County
Matthew M. Dean
23 July 98

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Craig W. McVean, in a field survey on Oct. 9 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-13 - GLO - Set 1/4 Sec. Post - J. Hodgson - 1837
Beech 12" N87°W 34L.
Maple 14" N47°E 20L.
- A.O. Temple - 1892 - FND. STP. of Beech 12" N87°W 34L. & Maple 14" N47°E 20L.
Set 4" Iron in 3' of 3" Dia. Tile.
Pine Stp. 24" N25°W 71L., Pine Stump. 24" S65°W 6L.
- LCRC L.1, P.283 - K.J. Ostling - 1972
FND. Temple Mon. and his Wit.
Left 1/2" Bar in 3" Vit.Tile in place. Add Cedar Post.
W. Oak 9" (Clp. 3) N20°E 61.0; Cherry 20" S28°E 32.8'
- LCRC L.3, P. 12 - C.F. Roser - 1991
FND. Temple Iron as FD. in 1972 DNR Survey.
Reset Cedar Post., 12" W. Oak - Clp. - 3
N20°E 60.8', 17" R. Oak S84°W 90.1 - Slope
- DNR Sur. Proj. #72-13 - K. J. Ostling - 1972
- DNR Sur. Proj. #26-93465 - C.F. Roser - 1991

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 - Standard 1/4 Corner Common to Sec. 34, T19N, R9W - FND 1/2" Iron Rod in Tile per LCRC's of Record. Monument in S. End at bowl area, open to the North. Monument accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 - Drove 1" x 48" Iron Pipe w/4" DNR Alum.Cap over 1/2" Iron Rod in Tile. Built Ring of Stone. FND. Cedar Post NNW 1.3'. Set blue Carsonite post 1'S. N20°E 61.55' to Set N&T in NW Side Tri. 12" R. Oak (CFR, KJO) S84°W 90.33' to Set N&T in SW Side 18" R. Oak - F. Scribed 'NBT' (CFR) N70°E 72.56' to Set N&T in S. Side 3" R. Oak S39°W 46.89' to Set N&T in N. Side 7" R. Maple scribed 'XBT' West 25.23' to H-1, T18N,R9W

OSCEOLA COUNTY REGISTER OF DEEDS
98 OCT 21 PM 4: 13
Nancy Campbell



Signed by Craig W. McVean
Surveyor's Michigan License No. 39088

Date 10/21/1998