

SURVEY & REMONUMENTATION

DEC 18 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in Osceola Located in: Corner Code#

1. Public Land Survey T 19 N R 9 W K-4
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R

3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

OSCEOLA COUNTY
 REGISTERED DEEDS
 00 OCT 11 AM 9:49
 Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on April 10, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

K-4 - 1/4 Corner common to Sections 11 & 12, T19N, R9W

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|---|--|
| <p>1838 - S. Sibley, G.L.O.
 #1 - 10" Hemlock S6°W 12 Links
 #2 - 14" Hemlock N55°W 12 Links</p> <p>1892 - A.O. Temple, Co. Sur.
 Remonumentation of T19N, R9W
 "Found accessory #1 dead with marks on it".
 Set 3" Clay Tile.
 #3 - 30" Pine Stump S35°E 74 Links
 #4 - 26" Pine stump S21°W 64 Links</p> | <p>Undated Co. Sur. Twp. Notes
 Pipe and Tile.
 #5 - 20" Pine West 12.2'
 #6 - 6" Hemlock N15°E 90'
 #7 - Distance South = 2616.8'</p> | <p>1988 - R.L. Wetherell, LS 24624
 L.C.R.C. - Liber 02, Pg. 305.
 "Found 2" Pipe and Tile".
 Set 1/2" Iron in 2" Pipe.
 #5 - 48" W. Pine S84°W 13.10'
 #8 - 8" Elm N81°E 50.63'
 #9 - 14" Maple S20°W 20.60'</p> |
|--|---|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1/2" Capped rebar (LS 24624) inside a 2" pipe which is inside the 3" Clay Tile (broken). The corner is in line with an old fence to the West and at the extension of centerline of seasonal roads North and East.


Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Found in good condition (50"), #6 Found in good condition, #7 Measured 2617.62' #8 Found dead, #9 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I placed a 1" x 18" Pipe with an Osceola County Remon Cap in the center of the 2" pipe, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 16" Hemlock N15°E 91.1' (center of tree) #6
- 16" Maple S20°W 20.51' (60d spike in E. side) #9
- 18" Maple N18°W 77.84' (60d spike in E. side)
- 5" W. Pine N45°E 61.12' (60d spike S.E. side)
- 10" Maple (in clump) S23°E 72.84' (60d spike W. side)

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Osceola County
R.L.W.
8-17-00



Signed by Robert L. Wetherell
 Surveyor's Michigan License No. 24624

Date August 22, 2000

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 ADAPTED FOR WORD PROCESSING JANUARY, 1999