

NOV 16 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>9W</u>	<u>L13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Osceola County

Matthew M. Deane
 23 July 98

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Craig W. McVean, in a field survey on June, 18 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

L13 -GLO- Set 1/4 Post-J. Hodgson-1837
 Beech 12" N84°W 18L., Beech 10" N64°E 44L.
 -A.O. Temple-1892-Frd. Stps. of Beech 12" N84°W 18L. & Beech 10" N64°E 44L., Evidence positive -Set tile & iron Mon. Pine Stp. 27" N39°E 29L., Pine Stp. 30" N56°W 23L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L13- Standard 1/4 cor. common to Sec. 36, T19N-R9W - Found 1/2" iron rod in 3" dia. vit. tile monument and Pine Stp. BT's per Temple. Found 6" dia. cedar guard post lying on ground. N-S sand trail rd. is 245' E. Monument is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L13 -Drove 4" DNR Alum. Cap on 1"X 48" iron pipe over 1/2" iron in tile. Built ring of stone. Reset 6" cedar post on E side. Set Carsonite post 1' N. N61°W 16.30' to set spike in CL. 30" W. Pine Stp. Remains(AOT) N39°E 19.70' to set spike in CL. 27"W. Pine Stp.w/3 face notches(AOT) N33°W 60.08' to set N&T in E side 8" R. Oak scribed 'XBT' S39°W 3.12' to set N&T in NW side 19" B. Cherry scribed 'XBT' S72°E 48.34' to set N&T in SW side 8" B. Cherry scribed 'XBT' N3°E 69.31' to set N&T in W side 5" R. Maple scribed 'XBT' East 22.97' to L-1, T18N,R9W

James Campbell
 98 OCT 21 PM 4: 14
 OSCEOLA COUNTY
 REGISTER OF DEEDS



Signed by *Craig W. McVean*
 Surveyor's Michigan License No. 39088

Date 10/21/1998