

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 19 ^{N.} _● R. 10 ^{W.} _●	C-3; D-2
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _● S., R. _____ E. _● W. _●	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _● S., R. _____ E. _● W. _●	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 18, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-3 Fd. ½"x3"x29" iron over two 3" tiles (buried in road); in line with fences to E & W. Fits 1917 Geo. Johnson survey of Sec. 5 whose notes indicate tile & rod (probably Temples - Roser comment).
- D-2 Fd. 1¼" pipe as set for ctr. of Sec. 5 in 1917 by Geo. Johnson whose notes are on file with Clint Cole, Lake County Surveyor. Also fd. both of Johnson's wit's. Accepted Johnson's pipe for ctr. of Sec. 5 as it was previously recovered & accepted by RLS Jack Erickson in survey of part of the SE¼ of Sec. 5. Corner falls in N-S fence remains. The computed straight line intersection of one-quarter lines is 25.1' N & 10.5' W of Johnson's pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3		D-2
Fd. ½"x3"x20" Iron		Fd. 1¼"x24" pipe; added ced. post
2-3" Maple N75°W	27.48	w/loc. tag
Power Pole N85°E	62.05	12" Cherry S70°E
Ctr. N-S gravel road		23" W. Pine S20°W
Due W 5'		13" Hemlock S50°W
		¼ old RR grade Due E 130'

SIGNED BY _____

Carl F. Roser

DATE 7-9-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

CHIEF OF SURVEY PARTY


DATE _____

APPROVED AND SIGNED BY _____

MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

LEROY TOWNSHIP
OSCEOLA COUNTY