

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 19 N. R. 10 ●	D-1; E-3
2. PROPERTY CONTROLLING IN SECTION 5, T. 19 N. R. 10 ●		5
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 6, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. - Description of original monument and accessories and/or subsequent restoration

C. (continued)

5
Set 5/8"x40" rerod w/RLS Cap
& cedar post w/loc. tag
4" W. Pine N20°W 55.3
4" W. Pine S80°W 80.8
Fd. 3/4" pipe N07°00'W 19.61

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-1** Reestablished N $\frac{1}{4}$ cor Sec. 5 equidistant between the NE & NW cor of Sec. 5 as noted in Geo. Johnson's minutes of survey of Sec. 5 & on line between the S $\frac{1}{4}$ cor & SE cor of Sec. 32 (T20N-R10W). Corner falls on the approx. edge of SE'ly bank of Pine River (course NW'ly) as so noted in Johnson's notes. Johnson surveyed & subdivided Sec. 5 dated April 25-30, 1917; the notes are on file with the Lake County Surveyor Clint Cole. Also see land corner record for S $\frac{1}{4}$ Sec. 32.
- E-3** Found and accepted $\frac{1}{2}$ " rerod by RLS Jack Erickson.
- 5** Established N 1/8 cor on N-S $\frac{1}{4}$ line per G.L.O. survey and plat.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p style="text-align: center;">D-1</p> <p>Drove 1"x60" pipe w/DNR cap & set cedar post w/loc. tag</p> <p>5" Cherry Due E 42.0</p> <p>4" Elm Due N 20.7</p> <p>11" Cedar S50°W 69.3</p> <p>S$\frac{1}{4}$ 32 T20N-R10W S89°03'W 30.81</p> <p>Set 5/8"x35" rerod & ced post w/loc tag N89°03'E 405.00</p> <p>Set 5/8"x40" rerod & ced post w/loc tag S01°40'E 180.00</p>	<p style="text-align: center;">E-3</p> <p>Fd. $\frac{1}{2}$" rerod w/RLS Cap</p> <p>7" Scotch Pine N45°W 72.62</p> <p>22" Maple S75°E 50.08</p> <p>6" W. Pine S20°E 73.50</p> <p>9" R. Pine N45°E 53.96</p> <p>Set ced post w/loc tag N45°E 47</p>
---	---

SIGNED BY Carl F. Roser

DATE 7-9-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

DATE _____

APPROVED AND SIGNED BY _____

DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

LEROY TOWNSHIP
OSCEOLA COUNTY