

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 19 <sup>N.</sup> <input checked="" type="radio"/> R. 10 <sup>W.</sup> <input checked="" type="radio"/>	D-3; E-2
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ <sup>N.</sup> S., R. _____ <sup>E.</sup> W. <input type="checkbox"/>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> S., R. _____ <sup>E.</sup> W. <input type="checkbox"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 23, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:


A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-3 Fd. 1/2" rod beside two tiles per RLS Jack Erickson. Fits 1917 Geo. Johnson survey of Sec. 5 whose notes indicate tile & rod (probably Temples - Roser comment).
- E-2 Restored E 1/4 corner Sec. 5 per RLS Jack Erickson survey of Sec. 5. Jack found rod (believed to be Temples rod & tile, Roser's comment). Corner fits Geo. Johnson 1917 survey of Sec. 5. Ctr. N-S trail Due W, 10'±. Ctr. trail E Due N 21'±. Corner is in line with old fence E'ly.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	D-3		E-2		
Fd. 1/2" iron beside 2 tiles; added cedar post w/loc. tag			Set DNR Monument, buried		
5" Maple N50°E	12.35		8" R. Pine S45°E	42.98	
6" Maple S20°W	17.42		8" R. Pine N50°E	70.30	
7" Maple S55°W	16.00		15" Maple S60°W	73.41	
			Set cedar post w/loc. tag		
			Due E	33'	



SIGNED BY Carl F. Roser DATE 7-9-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ LEROY TOWNSHIP  
OSCEOLA COUNTY