

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>5</u> , T. <u>19</u> , R. <u>10</u> W.	N. _____ E. _____ S., R. _____ W. _____	<u>2; 3; 4</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 26, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2 Reestablished E 1/8 cor on N line Sec. 5, equidistant & on line between the NE & N 1/4 cor of Sec. 5. Fd. pipe at old fn. cor. (fn. E-W-N, see item "C") fits Geo. Johnson's wit. from his sur of 5 in 1917; Johnson's cor not accepted by this survey as it was poorly set & fn. was constructed N from it (in error) without knowledge of double corners on twp. line.
- 3 Set 5/8"x34" rerod for SW cor. of N fri 1/2 of NW fri 1/4 of Sec. 5; established proportionate measurement to G.L.O. (run-out sec.).
- 4 Reestablished ctr. of NW 1/4 of Sec. 5 per G.L.O. survey & plat. Fd. 1 1/4" pipe (item "C") incorrectly estab. by Johnson in 1917 (did not consider run-out N to twp. line).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2	3	4
Set 5/8"x35" rerod & cedar post w/loc. tag	Set 5/8"x34" rerod & cedar post w/loc. tag	Set 5/8"x40" rerod w/RLS cap & cedar post w/loc. tag
2" R. Pine N40°W 15.9	7" Maple N10°E 21.3	3" W. Pine N15°E 53.8
4" W. Pine S25°W 31.9	5" Ash S55°W 13.6	5" W. Pine S85°E 46.4
Fd. pipe at old fn.cor. (fn. E-W & N) N68°10'W 12.8	Fd. 1 1/4" pipe S02°50'W 25.99	Fd. 1 1/4" pipe at old fn. cor. (fn. N-S-E) S76°36'W 8.20
E 1/16 on S line Sec. 32 (T20N-R10W) S89°03'W 30.12	N05°58'E 6.40	
	Ctr. N-S trail Due W 41'	

SIGNED BY Carl F. Roser

DATE 7-9-80



SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

LEROY TOWNSHIP
OSCEOLA COUNTY