

SURVEY & REMONUMENTATION


DEC 13 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in <u>Osceola</u>	Located in:	Corner Code#
1. Public Land Survey	T 19 N R 10 W	C-5
	T R	
	T R	
	T R	
2. Property Controlling S T R in Section	S T R	
	S T R	
3. Miscellaneous S T R Property in Sec.	S T R	
	S T R	
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		


 OSCOLELA COUNTY
 REGISTER OF DEEDS
 00 MAY -5 PM 2:51
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on March 22, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

C-5 - Section corner common to Sections 7, 8, 17 & 18, T19N, R10W

A. Description of original monument and accessories and/or subsequent restoration:

1838 - S. Sibley, G.L.O.

- #1 - 6" Beech N84°E 14 Links
- #2 - 6" Sugar N75°W 6 Links

Undated from Co. Sur. Twp. Notes

- "Tile and Rod".
- #4 - 2" Elm South 48'
- #5 - 16" Maple N.W. 74'

1997 - R.L. Wetherell, LS 24624

- L.C.R.C. - Liber 03, Pg. 146
- Found Clay Tile.
- #8 - P. Pole N73°E 104.69'
- #9 - 10" W. Pine S41°W 37.39'
- #10 - 9" W. Pine S22°E 40.42'
- #5 - 24" Maple N17°W 74.75'

1891-1904 - Temple/Trumbull

Remonumentation of T19N, R10W
Set 3" Clay Tiles

1980 J. Erickson, LS 16929

L.C.R.C. - Liber 02, Pg. 165
Survey recorded Liber 374, Pg. 490.
"Found Tile and Iron".

1919 - F. McClung, Co. Sur.

#3 - Distance North = 2524'

- #5 - 20" Maple N25°W 75.55'
- #6 - 5" Maple N45°E 105.60'
- #7 - 14" Maple S20°E 85.55'

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:

I found a 1/2" Iron in center of 3" Clay Tile and cinders. Corner is in line with fence to the South and centerline of road to South & 2.5 feet South of centerline of road East and West.


Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Measured 2522.53', #4 Gone, #5 Found in good condition, #6 Found in good condition, #7 Found S7°E 86', #8 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1/2" Iron with a 1" x 18" Iron Pipe with Osceola County Remon Cap, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- P. Pole N73°E 104.69' (Nail S.E. side) #8
- 24" Maple N17°W 74.45' (60d spike E. side) #5
- 10" W. Pine S41°W 37.39' (60d spike N.W. side) #9
- 9" W. Pine S22°E 40.42' (60d spike N.E. side) #10

APPROVED LAND CORNER
P.A. 245 OF 1990
Osceola County
R.L.W.
4-20-2000



Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date April 25, 2000