

**SURVEY &
REMONUMENTATION**

JUN 09 1997

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**

Osceola	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>19N</u> R <u>10W</u>	<u>F-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
24 April 1997

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung, in a field survey on Apr 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Act 132:
Liber 433, Page 59
Dated: 24 Sept
Set 1/2" rod
South 1/2" rod 33.
N10E Corner fence Post 36.25'
S19W P.Pole 72.40'

Unrecorded by McClung
Power Pole S12W 72.3'
6" Cherry S48W 41.7'
Fence Post N6E 31.1'
Top of Guy Anchor S22W 49.2'

continued on back

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2' crooked rerod, at intersection of 1/4 line, at surface in road. Placed Osceola County Monument over 1/2" rerod 3" below road surface. Corner is in fence row North and South. Position of this corner was check by McClung and missed by less than 0.10' each way, which will very because the E 1/4 position has been moved.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner F-6. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
Power Pole S12W 72.3 feet. (Ray)
6" Cherry S48W 41.7 feet.
Fence Post N6E 31.1 feet. (Ray)
Top of Guy Anchor S22W 49.2 feet.

Signed by *Matthew McClung*
Surveyor's Michigan License No. 13037

Date April 18, 1997



OSCEOLA COUNTY
REGISTER OF DEEDS

97 APR 30 PM 12:33

Nancy Crawford

Ray

F-6 to G-6	2633.80 feet.
F-6 to F-5	2596.17 feet.
F-6 to E-6	2618.82 feet.
F-6 to F-7	2608.04 feet.

McClung

F-6 to G-6	2634.28 feet.
F-6 to F-5	2595.61 feet.
F-6 to E-6	2518.98 feet.
F-6 to F-7	2608.70 feet.

SURVEY &
REMONUMENTATION

JUN 09 1997

COMMISSION