

SEP 10 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

OSCEOLA COUNTY REGISTER OF DEEDS

98 JUL 23 PM 12:39

For corners in

Osceola  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 19 R 10W      H-6
- T    R
- T    R
- T    R
- 2. Property Controlling    S    T    R
- in Section                S    T    R
- 3. Miscellaneous            S    T    R
- Property in Sec.         S    T    R

*Nancy Crawford*

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*28 May 1998*  
*Matthew McClung*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Matthew McClung in a field survey on 5-22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
This corner was not set by the original Government survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Set Osceola County Monument 1 1/2" below road surface. Corner is in C/L of E & W road. This corner is set at the intersection of the One Quarter lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Corner H-6. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
E. end North side concrete abutment N34W 21.40 feet.  
E. end South side concrete abutment S48W 25.40 feet.  
E. joint drain headwall N30E 22.0 feet.  
E. joint drain headwall S14E 20.46 feet.



Signed by Matthew McClung  
Surveyor's Michigan License No. 13037

Date 23 July 1998