

SURVEY &  
REMONUMENTATION

FEB 16 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

OSCEOLA COUNTY  
REGISTER OF DEEDS

98 NOV 23 AM 10:37

*Nancy Crawford*

For corners in

Osceola  
(County)

Located In:

Corner Code #

- |                                    |                             |       |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey              | T <u>19</u> N R <u>10</u> W | J-6   |
|                                    | T ___ R ___                 | _____ |
|                                    | T ___ R ___                 | _____ |
|                                    | T ___ R ___                 | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___           | _____ |
|                                    | S ___ T ___ R ___           | _____ |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___           | _____ |
|                                    | S ___ T ___ R ___           | _____ |

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*Matthew McClung*  
8 Oct 1998

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Matthew McClung in a field survey on 10-7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- |  |  |
|--|--|
| Act. 132, Liber 492, page 511<br>Set P. K. nail<br>S5W Guard Post 14.72'<br>S40W Guard Post 26.72'<br>North Guard Post 16.93'<br>N40E Guard Post 34.47 | Act 132, Liber 521, Page 575<br>No Witnesses.<br><br>Act 132, Liber 535, page 507<br>5/8" capped iron<br>No Witnesses. |
|--|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Excavated to just below asphalt and found 5/8" iron with cap 13037. Placed Osceola County Monument in position of survey iron. Corner is 1' south of C/L E & W Road and in fence rows N & S. When I did the survey Liber 521, page 575, I found the P.K. nail set by Ray. I intersected the quarter lines and my center position was 0.03' north and 0.27' east of the Ray position for the center. I placed the center at the Ray P.K. nail.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner J-6. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
Survey Iron North 33.0 feet. No. 13037  
Telephone Pedestal S8E 29.1 feet.  
Guard rail post N65W 35.3 feet.  
Guard Rail post N50E 34.3 feet.



Signed by *Matthew McClung*  
Surveyor's Michigan License No. 13037

Date 23 Nov 98