

SURVEY & REMONUMENTATION

NOV 02 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola
(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-------|---------------------------|---------------|
| 1. Public Land Survey | | T <u>19</u> R <u>10</u> W | <u>H-5</u> |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ | T ___ R ___ | <u>Seg #2</u> |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

Recorded to correct
Liber B, Page 201 re-
recorded 23 July 1998.

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
28 May 1998

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung in a field survey on 5-21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5								●					
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor Sylvester Sibley July 7, 1938. Set 1/4 post 40.10 chs. from East.
Hemlock 10" S77W 14 lks.
Hemlock 14" N31E 6 lks.

From 1891 to 1904 approximately, Osceola County had a remonumentation program in which surveyors Temple and Trumbell did the work. For most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" X 18" long pipe bent over at surface. Excavated to 8" below surface and found 1/4" rod in center of tile. Placed Osceola County Monument in center of tile 4" below surface. Corner is in centerline of road to west and in center of dead end turn around.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner H-5. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
Telephone pedestal S44W 50.85 feet.
Telephone Pedestal N46W 41.0 feet.
12" Ash N20E 81.0 feet.
Power Pole N60E 88.0 feet.



Signed by Matthew McClung
Surveyor's Michigan License No. 13037

Date 15 Oct 98