

**SURVEY &
REMONUMENTATION**

SEP 10 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>7W</u>	<u>J-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

25 May 1998
Matthew M. Clung

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung in a field survey on 5-25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

The corner was set by deputy surveyor Frances Coleman on Oct. 29, 1856.
Reestablished old Qr. Sec. post 40.16 chs. from east. (resurvey)
W. Pine 14" N6E 62 lks.
W. Pine 14" S39W 25 lks.

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found monument box at surface, in fence line N & S and 3' South of C/L E & W highway M-61. Found State Monument 4" below surface.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner J-5 is MDSH&T monument in monument box.

- R/W Marker S04E 71.1 feet.
- R/W Marker N04W 79.0 feet.
- Red Oak 6" N28W 87.50 feet.
- E. end culvert to North North 48.0 feet.

Signed by Matthew M. Clung
Surveyor's Michigan License No. 13037

Date 23 July 1998

SURVEY &
REMONUMENTATION

SEP 1 0 1998

SECTION

OSCEOLA COUNTY
REGISTER OF DEEDS

98 JUL 23 PM 12:40

Nancy Crawford

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been entered in the County surveyors records.

MDSH&T Corner card.
Found 2 1/2" tile placed 5/8" rod
inside tile.
13" Oak S15E 57.20'
17" Oak N20W 46.04'
9" Oak N37E 70.56'

Act. 74.
Liber 2, page 151, by McClung
Found Monument box.
Mon. box in M-61.