

SURVEY &
REMONUMENTATION

SEP 10 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OSCEOLA COUNTY
REGISTER OF DEEDS

98 JUL 23 PM 12:40

For corners in

| | | |
|---------------------------------------|--|---------------|
| <u>Osceola</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>19</u> R <u>7</u> W | <u>L-4</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

APPROVED LAND CORNER
P.A. 545 OF 1990
Osceola County

28 May 1998
Matthew M. Clung

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung in a field survey on 5-25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not set by original survey.
Act 74
Liber 1, Page 356
Set Iron & cap
Triple B. Oak N25W 13.45'
3" N. Pine S80E 25.8'
F.P. N60W 50.8'

Liber 2, Page 157
Fd Iron with RLS cap 13037
Iron w/RLS Cap
16' triple cluster N25W 13.20
16" tree S25W 61.92'
14" tree N83W 46.11'
14" tree S45E 34.92'

(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cap and Iron at surface. adjacent to cedar post. Placed Osceola County Monument over 5/8" rod at surface. Note: Corner is 47+-East of North and South Fence and 17 feet South of Extension of East and West fence. Corner is set at intersection of one quarter lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner L-4 is a Osceola County Monument which is a 3" brass cap mounted on a 1' pipe 18" in length.
Red Oak 6" N22E 17.5 feet.
Power Pole S38E 33.3 feet.
Double B Oak (was triple) s. most 18" N32W 13.1 feet. O.B.T.
Red Oak 16" N86W 46.3 feet. O.B.T.
Fence Post N72W 50.85 Feet O.B.P.

Signed by Matthew M. Clung
Surveyor's Michigan License No. 13037

Date 23 July 1998

