

SURVEY & REMONUMENTATION

NOV 02 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--|---------------|
| 1. Public Land Survey | T <u>19</u> N <u>7</u> W | <u>M-5</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u>Seg #2</u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Rerecorded to correct Liber B, Page 234 re-recorded 23 July 1998. *Seg 1*

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
28 May 1998

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung in a field survey on 5-25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

The corner was set by deputy surveyor John Hodgson on Dec. 7, 1856. Set Post Corner 80.00 chains from the South. (resurvey)
Pine 10" S31W 43 Lks.
Pine 8" N57W 74 lks.

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Monument Box in C/L of M-61. Found State Monument.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M-5 is a MDSH&T monument.

- DNR Post North 50.35 feet.
- East end of Culvert S12E 43.3 feet.
- West end of Culvert S20W 46.9 feet.
- Red Pine 16" N50E 175.9 feet.

Signed by *Matthew McClung*
Surveyor's Michigan License No. 13037

Date 15 Oct 98