


NO. 8 of 16



Osceola COUN

T 19 N, R 8 W

ITEM 2 SEC. 29 CODE 8

Sec 29

DESCRIPTION W 1/16 on E-W 1/4 line

DATE SET 3-7-80 RH&KV

Set 1 1/4" x 6' pipe welded on top

(C) COR. MON. of 7' steel in post in 2' muck swale:

W	Set 5/8" x 34" re-rod	N 88° 53' E	235.0'
I	# Ced Post w/loc tag		

T	Set 5/8" x 34" re-rod	N 3° 29' W	75.0'
N	# Ced Post w/loc tag		

E	Edge lake	Due E	196' ± 6'
---	-----------	-------	-----------

S	" "	" N	35' ± 6'
---	-----	-----	----------

S	" "	" W	37' ± 6'
---	-----	-----	----------

RESTORATION PROCEDURES (A and/or B)

ⓑ Established W. 1/8 Cor.

on E-W 1/4 line per

std. B.L. M instructions.

Corner falls in Big Long

Take (set pipe) and is on our brushed out tree line.

to N. & E.