



NO. 10 of 16

Osceola COUNTY

T 19 N, R 8W

ITEM 2 SEC. 29 CODE 9

DESCRIPTION E 1/16 on E-W 1/4 line

DATE SET 6-12-80 (✓ 7-16-80) R# 4KV

(C) COR. MON. set 5/8" x 34" re-rod w/RLS cap

W & ced Post w/loc tag

I

T N-S smooth Due W 163' ±

N wire on tree's

E 3" R. Oak N 45° E 7.1

S 3" Ash S 35° E 11.7'

E

S 3" R. Oak S 85° W 4.9'

RESTORATION PROCEDURES (A and/or B)

(B) Established E 1/8 Cor. on

E-W one-quarter line,

mid-way & on line between

E 1/4 Cor. & ctr. of S-29. An

un-used crooked E-W trail

is 163' ± south. A beautiful

20" W. Birch is 160' west.