



NO. 2 of 16

Osceola COUNTY

T 19 N, R 8 W

ITEM 1 SEC.        CODE D-9

DESCRIPTION N 1/4 Sec 29

DATE SET 6-12-80 (✓ 6-12-80) (7-16-80) RH&KV

(C) COR. MON. Fd - Tile's & 5/8" x 20" iron rod;  
 added DNR Mon & Ced Post

W  
I  
T  
N  
E  
S  
S  
E  
S

16" Beech N 30° W 62.4'

11" Maple N 25° E 76.0'

11" W Oak S 30° W 88.1'

Fn Cor, E-W-N Due S 78'  
 (in Beaver Pond)

RESTORATION PROCEDURES (A and/or B)

(B) Found 3- 3" files w/ cinders  
 and 5/8" x 20" iron lying on  
 ground. Brass Cap monument  
 was gone. Replaced Tile  
 with Dept. monument.  
 Corner fits 3-McClung Wits.