

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**OSCEOLA**

(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>19N</u> R <u>8W</u>	<u>B-10</u>
	T _____ R _____	<u>B-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>30</u> T _____ R _____	<u>12</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CARL F. ROSER, in a field survey on FEBRUARY 9, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

B-10                                      B-11                                      12

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>B-10</u> ACCEPTED OSCEOLA CO MON FOR CTR. SEC. 30. RLS, MATT MCCLUNG, FB HIT BUT NO STAKE IN 1973. MATT SAID THIS COR SET BY HIS DAD, FRANK MCCLUNG. THIS FITS BOTH OF MATT MCCLUNG'S BT'S & 2, RLS, H. FLUNARTY (1976) BT'S.	<u>B-11</u> FB OSCEOLA CO MON FOR S1/4-SEC. 30, RESTORED BY RLS, MATT MCCLUNG IN 1973. MCCLUNG FB WITNESS PROBABLY HIS DADS, BUT NO STAKE.	<u>12</u> ACCEPTED 3/4" SMOOTH IRON ROD W/MATT MCCLUNG'S RLS CAP#13037. FB & USED ALL 3, RLS, H. FLUNARTY (1976) BT'S.
---	---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>B-10</u> FB OSCEOLA CO MON, ADDED CED. POST. 19° R. OAK N35°N 5.4' 19° R. OAK S80°E 26.4' 17° R. OAK S25°N 43.7' CTR N-S TR. DUE E 16'	<u>B-11</u> FB OSCEOLA CO MON, ADDED CED. POST. 3° R. OAK N15°N 28.1' 2° R. OAK S45°E 18.9' 2° MAPLE N85°N 6.3' 2° R. OAK N75°N 10.6'	<u>12</u> FB 3/4" IR ROD W/RLS CAP & ADDED CED. POST W/LOC TAG. 13° R. OAK N30°E 5.9' 31° R. OAK S15°E 16.5' 18° R. OAK DUE W 30.6' CTR TR N'LY DUE E 22'
---	---	---



Signed by Carl F. Roser 02-05-91 Date \_\_\_\_\_  
 Surveyor's Michigan License No. 12028