LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola	Located In:	Corner Code #	
1. Public Land Survey	T 19N R 8W	A13	
	TR		
2. Property Controlling S in Section S	T	***************************************	
3. Miscellaneous 'S			
Property in Sec. S	TR		Register of Deeds Stamp & File Numb
4. Lot No, Recorded	Plat		
5. Private Claims			A B C D E F G H I J K L M
I, Craig W. McVean, in a field surstate that under requirements of P.A. 74 mentioned in lines 1 and 2 above were therefore as required in the current mediates Department of the Interior, Burea Court of Law and /or that the corner powers in conformance with the rules of the Decree of a Court of Law; established, found as exp	b, Michigan P.A. of 1970, the corr in conformance with regulations a mual of survey instructions of the u of Land Management or by a de pints mentioned in lines 3, 4 and 5 m Michigan Board of Land Surveyo	ner points ind rules United cree of a is above rs or by a	2 6 5 4 3 2 1 1 3 4 7 8 9 10 11 12 5 6 18 17 16 15 14 13 7 7 8 19 20 21 22 23 24 9
NOTE: Not more than 2 corners, a	II in the same town and range	. may be recorded on this	10-30-29-28-27-26-25
cartificate.		, ,	11 32 33 34 35 36
A. Description of original monumer	nt and accessories and/or sub	sequent restoration:	
A-13 - GLO- Set Post-J. Hodgson-1 Maple 7" N41°W 37L., Bl. C -A.O. Temple-1892-Old witness of Pine Stp. 15" S40°E 34L., P -Set tile 4' Iron in 3-3"x 12" tiles fill -LCRC -L.1, P. 281- K.J. Ostling-19 1/2" bar in 3" Dia. Vit. Tile. Added 27" B. Oak N34°W 65.4', 15" W. R. Maple 4-clp. S50°E 19.9', CL. o Course NE-SW	ak 9" N27°E 44L. local survey & old stake. ine stp. 18" N70°E 7L. ed with cinders. 72- Fnd.Temple Mon. & Wits I Cedar post Oak N23°E 48.8', 8"	3.	
B. Description of corner evidence f	ound and/or method applied i	n restoring or reestablishing	g corner:
A-13 - Township cor. common to Se T19N-R8W, Sec. 1 ,T18N-R9W & S 1/2" iron rod in 3" dia. vit. tile monu Monument is accepted as the best a position of the original corner.	ec. 6 ,T18N-R8W - Found ment per Temple and LCRC.		
C. Description of monument for corr	er and accessories establishe	d to perpetuate locating th	e position of the corner:
<u>A-13</u> - Added 2" A.C. on 1/2" iron i	n tile with Concrete and		
stones around. Fnd. cedar post on N	W side.		SLITE OF MICHIGA
Set Carsonite post 1'SE	Pina On a 10 f		St Or ICAIO
S45°E 22.16' to set N&T in face 15' notches(AOT)	Pine Stp.w/3 face		15
notenes(AOT) N35°W 66.44′ to set N&T in E side (ROTE Oak IK IOI		# CRAIG W. \ \ \
N22°E 48.98' to set N&T in SE side			MCVEAN .
S43°W 32.66' to set N&T in N side			PROFESSIONAL
N76°E 47.17' to set N&T in N side 1	8″ R. Oak scribed 'XBT'		SURVEYOR OF SEIONAL IN
Signed by Crine W. 4	Ne Ven		Date 10/14/1998
Surveyor's Michigan License No.	39088		