

**SURVEY & REMONUMENTATION**

AUG 29 1995

**LAND CORNER RECORDATION CERTIFICATE**

**COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Osceola (County)	Located In:	Corner Code #
	19N 8W	G-9
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*29 June 1995*  
*Matthew M. McClung*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Matthew McClung, in a field survey on 19 June, 191995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

The corner was set by deputy surveyor Sylvester Sibley on July 7, 1838. Set wood post 80.00 chains from the South.

Beech 16" N26.5W 49 Lks.

Beech 8" S30.5E 47 Lks.

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 20 penny spike 2" below surface. Found 3/4" bar 18" (pointed) 7" below surface. Found 1" pipe 18" below surface, 20" long. Excavated to 36" and found no other evidence of corner. Corner appears to be in a cut area, however I can not estimate depth of cut. No top soil was found in excavation.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner G-9, is Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.

12" White Ash S60W 88.85 feet.

Power Pole N46W 72.25 feet

Telephone Pedestal N54W 38.31 feet.

10" Maple S34E 73.45 feet.

Signed by *Matthew M. McClung*

Date June 19, 1995

Surveyor's Michigan License No. 13037

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN. 1983

OSCEOLA COUNTY  
REGISTER OF DEEDS

95 JUL -6 AM 10:40

*Nancy Crawford*

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been recorded in the County records.

I have shown 1 P.A 132 Survey certificate by Clint Cole.

This corner is shown in the Hartwick Township book, on pages 46 thru 49 and pages 52 and 53.