

**SURVEY &
REMONUMENTATION**

JUN 09 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>19N</u> R <u>8W</u>	<u>L-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
24 April 1997

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Matthew McClung, in a field survey on Apr 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Hartwick Township Book
Pages 14 and 15
Dated May 29, 1902
Center = Iron
Pine Stump SW 22.2 feet.
Pine Stump East 33.5 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/4" pipe 9" above surface, 1.4 feet South of corner fence post with woven wire North, 3 barb South and single barb West. Removed pipe and placed Osceola County Monument in position of pipe, 6" above surface. Intersection of 1/4 lines is not determined.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner L-2. is Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
8" maple S35W 22.17 feet.
4" Hemlock (South of triple) S60E 57.0 feet.
12" Maple N34E 31.37 feet. E & W barb fence in tree.
5" Maple N34W 27.87 feet.
Approx. Southeast 80 feet from water in marsh.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Matthew McClung
97 APR 30 PM 12:32
OSCEOLA COUNTY
REGISTER OF DEEDS

Signed by *Matthew McClung*
Surveyor's Michigan License No. 13037

Date April 14, 1997

