

SURVEY & REMONUMENTATION

JUN 9 8 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>20</u> N <u>R9</u> W | G-9 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
24 April 1997

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung, in a field survey on 10-Oct-1976 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor Sylvester Sibley on July 7, 1838. Set wood post 80.00 chains from the South.

Sugar 26" N9E 11 lks.

Sugar 12" S39W 17 lks.

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" X 20" long iron shaft in monument box 6" South of centerline of East and West Road. Removed 1 1/2" shaft and excavated to 28" and found 1" iron pipe. Placed Osceola County Monument in position over 1" pipe in monument box. Road surface is cut approximately 4-5 feet from original.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner G-9. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.

5" W. Ash South 22.15 feet.

East most 8" Maple in Clump of 4 S62W 59.60 feet.

22" Walnut N80W 154.3 feet.

4" Red Pine S72E 114.95 feet.

Signed by Matthew McClung
Surveyor's Michigan License No. 13037

Date April 14, 1997



thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been entered in the County Surveyors records.

I have shown 1 LCRC: Liber 1, Page 428.

I have shown 3 PA 132: Liber 335, Page 667; Liber 547, Page 748, Liber 532, Page 796.

George Crawford
OSCEOLA COUNTY
REGISTER OF DEEDS
97 APR 30 PM 12:32

SURVEY &
MONUMENTATION
JUN 09 1997
COMMISSION