

**SURVEY & REMONUMENTATION**

FEB 25 1994

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Osceola

	Located In:	Corner Code #/
	20N 9W	K-11
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**APPROVED LAND CORNER**  
**P.A. 345 OF 1990**  
**Osceola County**

*Matthew McClung*  
8 Dec 1993

Register of Deeds Stamp & File Number

I, Matthew McClung, in a field survey on December 3, 191993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 The original corner was set by deputy surveyor Sylvester Sibley on July 7, 1838. Set wood post 80 00 chains from the South. 12" Birch tree for corner.

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found Osceola County Monument at surface of asphalt at intersection of 130th Ave and 19 Mile Road. (Dighton) Removed monument which had been driven over a 1/2" rod making the corner 3' long. Found a square shank spike 8" long 1.65' below road surface. Found Tile at 2.3' below road surface. Reset monument and rod in center of tile, 6" below road surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Corner K-11. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
 R/W marker N35E 55.1 feet. OBM. McClung  
 34" W. Pine S25E 52.0 feet. OBT. from 1913.  
 20" Maple S35W 56.0 feet. OBT. McClung  
 Power Pole N55W 39.15 feet.



Signed by Matthew McClung Date December 2, 1993  
 Surveyor's Michigan License No. 13037

OSCEOLA COUNTY  
REGISTER OF DEEDS

93 DEC 10 PH 2:50

*Nancy Crawford*

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been recorded in the County records.

This corner is recorded in the Sherman Twp. Book Pages 32 and 33, with no description of object. Pine 12 S21E 80 lks.

PA. 74 certificate, dated 17 June. 1974, by McClung.

PA. 74 certificate, dated 20 Sept. 1974 by McClung.

One PA. 132 certificates, by McClung.