

**SURVEY &
REMONUMENTATION**

DEC 13 2000

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

For corners in Osceola	Located in:	Corner Code#
1. Public Land Survey	T 20 N R 9 W	M-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

OSCEOLA COUNTY
 REGISTER OF DEEDS
 00 NOV -2 PM 4:12
Mary Campbell

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on September 13, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

M-7 - Sec. corner common to Sections 13 & 24, T20N, R9W.

A-7 - Sec. corner common to Sections 18 & 19, T20N, R8W

A. Description of original monument and accessories and/or subsequent restoration:

1838- S. Sibley, G.L.O.

- #1 - 20" Sugar S45°W 58 Links
- #2 - 16" Sugar N65°W 17 Links

1915 - F. McClung, Co. Sur.

- #4 - Distance East = 2429.6'
- #5 - Distance North = 2638.4'
- #6 - Distance West = 2595'

Undated from Co. Sur. Twp. Book

- "Tile & Iron"
- #7 - 25" Maple N.W. 79'
- #8 - 7" Elm S.E. 41.8'
- #6 - Distance West = 2575.3'

1891 - L. June, Co. Sur.

- Remonumented T20N, R8W.
- "Found old corner with stone.
- Set 3" Clay Tile.
- #3 - 7" Beech S19°E 152 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found three (3) clay tiles with cinders staked on top of each other. Corner is 3 feet North of centerline of East and West road and in line with fence to North.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Did not measure, #5 Did not measure, #6 Did not measure #7 Found 40" Stump, #8 Gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 1" x 18" Iron Pipe with an Osceola Co. Remon Cap, and is accepted as a careful and faithful perpetuation of the position of the original corner.

- 9" Maple Clump S82°W 115.81' (60d spike N. side)
- 24" Maple S9°E 100.40' (60d spike E. side)
- P. Pole S19°E 70.64' (60d spike S.W. side)
- 28" Maple S64°E 65.43' (60d spike N. side)
- 8" Spruce N51°E 72.46' (60d spike E. side)

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Osceola County
R.L.W.
10-31-2000



Signed by Robert L. Wetherell

Date November 1, 2000

Surveyor's Michigan License No. 24624