

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. 20 N. R. 10	●	C-13; D-11
2. PROPERTY CONTROLLING IN SECTION 32, T. 20 N. R. 10	●	9
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ S. R. _____ E. W.	●	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 27, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-13 Fd. two 3" tiles (iron had been removed from tiles); added DNR mon. Corner falls at old fence corner, fn N & E. Fd. large w. pine stump West 59'; fits US line tree & Frank McClung wit. McClung notes call for tile & rod (probably by Temple). Also fits US line tree (stp now) ^{E 26"} w. pine stp., 444' mea, US was 455' to nearest 10 links. GLO survey calls this corner common to Sec. 31 & 32 (20-10) & Sec. 5 & 6 (19-10), no closing corner.
- D-11 Fd. 1/2"x36" pipe buried in old E-W dirt road grade that fits 3 McClung wits.
- 9 Established East 1/8 corner on E-W 1/4 line, Sec. 32, equidistant & on line between the center and E 1/4 corner of Sec. 32

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13	D-11	9
Fd. 2-3" tiles; added DNR Mon. & cedar post w/loc. tag	Fd. 1/2"x36" pipe; added DNR mon. & cedar post	Set 5/8"x40" rerod w/RLS cap & cedar post w/loc. tag
2-5" Maples N30°E 16.3	6" B.Cherry N75°E 10.86	6" W. Pine S55°E 15.6
4" Maple S50°E 26.9	3" Maple S50°E 20.90	3" Beech S65°W 5.4
7" Maple S85°W 41.6	21" Cedar S30°E 39.55	N-S fence Due W 43'
Ctr. Rd. N'y Due W 16'	Fd. 1" bolt S01°42'W 33.12	Ctr. RR grade Due E 142'±
	Ctr. Pine River Due W 168'	
	<i>R.O.W. fits 34' x N 9 3/4' S.</i>	

SIGNED BY

Carl F. Roser

DATE 7-9-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____

CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____

MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BURDELL TOWNSHIP
OSCEOLA COUNTY