

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 20 N. ● R. 10 W.	C-11; C-12; D-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 18, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-11 Fd. pick axe as noted in 1905 Co. records (Trumble or Temple) & also fd. one Geo. Johnson wit (no date). Ctr N-S grl. rd. Due W 2'; Ctr. grl. rd. Due S 2'; Cor. is in line with trail to E.
- C-12 Fd. 1/2"x19" iron buried in N-S grl. rd. that fits two Frank McClung wits. Corner is in line with fences to E & W.
- D-12 Estab. ctr. of Sec. 32 at intersection of 1/4 lines. A ced. stk. point & 3 old wits. by G. Johnson (1911-1917±) was set by only going around the SW 1/4 of Sec. 32 and is S01°49'W 55.05'. F. McClung later used this incorrect ctr. for an approx. survey for description (1940±) in NW 1/4 of Sec. 32

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11	C-12	D-12
Fd. 1"x24" iron rod over old pick axe standing on end.	Fd. 1/2"x19" iron rod; added 5/8"x40" rerod	Set 5/8"x40" rerod w/RLS cap & cedar post w/loc. tag
2" Sugar Maple S35°W 135.20	8" R. Pine S60°W 38.90	5" Maple N60°E 8.1
2" Soft Maple S45°E 47.46	9" R. Pine S80°W 58.62	8" Cedar S50°E 17.4
Set cedar post w/loc. tag S45°E 47'	Set cedar post w/loc. tag Due E 25'	8" Cedar S10°W 28.0
	Ctr. N-S grl. rd. Due E 2'	8" Hemlock S50°W 14.6
		Irreg. fn. remains N Due W 9'±

SIGNED BY Carl F. Roser DATE 7-9-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

OSCEOLA COUNTY
BURDELL TOWNSHIP

SURVEYOR'S MICHIGAN REGISTRATION NO. _____