

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. 20 ^{N.} <input checked="" type="radio"/> , R. 10 ^{W.} <input checked="" type="radio"/> | E-11; E-12; E-13 |
| 2. PROPERTY CONTROLLING IN SECTION _____ | T. _____, ^{N.} <input type="radio"/> , ^{S.} <input type="radio"/> R. _____, ^{E.} <input type="radio"/> , ^{W.} <input type="radio"/> | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____, ^{N.} <input type="radio"/> , ^{S.} <input type="radio"/> R. _____, ^{E.} <input type="radio"/> , ^{W.} <input type="radio"/> | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 7, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-11 Fd. 3/4" pipe in approximate center of gravel roads to N & W with trail road to E. Corner is in line with fence to S & fits one Frank McClung witness.
- E-12 Reestablished 1/4 corner equidistant & on line between sec. corners to N & S. An approximate corner by Lloyd Coal, 3/4" pipe stuck in ground is S85°24'E, 97.95'.
- E-13 Recovered SE corner Sec. 32 (20-10) as a fd. 1/2" rod in two 3" tiles (probably Temple). Fits G.L.O. distance to closing corner between Sec. 4 & 5 (19-10) to east very reasonable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| E-11 | E-12 | E-13 |
|--|--------------------------|---------------------------------|
| Fd. 3/4" pipe, buried 1' | Set DNR Mon. & ced. post | Fd. old 1/2" iron rod in 2-3" |
| 3-3" Apples S50°E 40.86 | 7" Cedar N35°E 26.1 | tiles; added ced.post w/loc.tag |
| Approx. ctr. 24"x30" stone, flush. S40°E 40' | 11" Maple Due E 18.6 | 12" S. Maple N10°E 32.5 |
| Set ced. post w/loc. tag Due S 33' | 8" Hemlock S25°E 19.8 | 13" S. Maple N40°E 41.9 |
| ROW fn. cor (fn. E & S) South 33' | Random West Due N 2.7 | Fd. 5/8" rerod N79°25'E 29.90 |
| ROW fn. cor (fn. W & S) South 22' | | NE S-5 (19-10) S89°51'E 29.44 |
| | | Old E-W fn. Due N 5' |

SIGNED BY _____ *Carl F. Roser* DATE 7-9-80
 SURVEYOR'S MICHIGAN REGISTRATION NO. 12028
 FOR STATE AND UNITED STATES AGENCIES:



SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BURDELL TOWNSHIP
OSCEOLA COUNTY