

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 20 N. R. 10 W. <input checked="" type="checkbox"/>	G-13
2. PROPERTY CONTROLLING IN SECTION 32 _____	T. 20 N. R. 10 W. <input checked="" type="checkbox"/>	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W. <input type="checkbox"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 26, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-13 Recovered SE corner Sec. 33 as a ½" rod in two 3" tiles (probably Temple's) as recovered by Frank McClung in Nov. 1920. Corner fits two McClung witnesses. Corner is in line with dirt road to N. Ctr. trail south is E 4'±. Ctr. dirt road east is N 19'±. Old ROW fence corner (fn. E & S) is 30'±S & 33'±E.
- 16 Established E 1/8 corner on the S line of Sec. 32, equidistant and on line between the S ¼ corner and SE corner of Sec. 32. Also see corner record for E 1/8 corner on N line of Sec. 5 (19-10).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13
 Fd. ½" iron rod in 2-3" tiles
 9" W. Pine S70°E 38.5
 16" Maple S40°E 23.5
 2" W. Pine S40°W 45.3
 Set cedar post w/loc. tag
 Due W 33'

16
 Set 5/8"x35" rerod & cedar post w/loc. tag
 4" W. Pine S30°E 34.4
 3" R. Pine S80°W 75.5
 Fd. pipe at old fn. corner (fn E-W & N)
 N73°57'E 19.0
 E 1/16 on N line S51°19N-R10W
 N89°03'E 30.12

SIGNED BY Carl F. Roser

DATE 7-9-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BURDELL TOWNSHIP
 OSCEOLA COUNTY