

FEB 4 2000

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

For corners in Osceola	Located in:	Corner Code#
1. Public Land Survey	T 20 N R 10 W	A-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

OSCEOLA COUNTY
 REGISTER OF DEEDS
 99 NOV 19 PM 12:10
Harvey Campbell

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 1 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: ONLY ONE CORNER MAY BE RECORDED ON THIS CERTIFICATE.
 W 1/4 Corner of Section 30, T20N, R10W

A. Description of original monument and accessories and/or subsequent restoration:

1838 S.Sibley
 #1- 12" Sugar S28W 29 Lk.
 #2- 10" Beech N13W 21 Lk.

1905 Burdell Twp. Book
 Page 12 & 13
 Dist. North 2650.56'
 Dist. South 2649.24'

Undated Burdell Twp Book
 Pages 16&17
 Iron
 #3- 20" Maple NW 74.5'
 #4- P.P. West 54.7'
 #5- Cherry S60W 16.6'
 Dist. North 2644.'
 Dist. South 2647.'

1992 M. McClung LS 13837
 Recorded Survey Lake County
 L.4, Pg. 278
 L.4, Pg. 280
 Pd. Iron & Cap 16929 (J. Erickson) wood stake
 Set Osceola County Monument
 #3- 42" Maple N34W 75.5'
 #6- 3" metal gate post N62E 37.95'
 #7- 3" metal gate post S86E 34.0'
 #8- 8" Maple N20E 87.09'
 Dist. North 2646.04'
 Dist. South 2645.51'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found Osceola County Monument in line with fences East and West and in the C/L of the road North and South.

Condition of the accessories are as follow: #1 Gone. #2 Gone, #3 Found in good condition, #4 Gone, #5 Gone, #6 Found in good condition, #7 Found in good condition and #8 Found in good condition.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I accept the Osceola County Monument (1 1/2" pipe with an Osceola County Remon Cap) as a substantial marker of the corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 42" Maple N34W 75.4' (Nail on NE side) - #3
- 3" Metal Gate Post N62E 37.95' (Center) - #6
- 3" Metal Gate Post S86E 34.0' (Center) - #7
- 8" Maple N20E 88.0' (Nail on NW side) - #8

Signed by Robert L. Wetherell Date Nov. 9, 1999

Surveyor's Michigan License No. 24624



APPROVED LAND CORNER
 P.A. 345 OF 1990
 Osceola County

10-21-99
R. L. W.