

SURVEY & REMONUMENTATION

SEP 15 1994

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber Page 127

For corners in
Osceola
(County)

Located In: Corner Code ##

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>20N</u> R <u>10W</u> | <u>E-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County

Matthew McClung
21 June 1994

Register of Deeds Stamp & File Number

I, Matthew McClung a field survey on June 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
The original corner was set by deputy surveyor Sylvester Sibley on 7 July 1838. Set wood post 40.00 chains from South.
Hemlock 14" N44W 14 lks.
Bl. Ash 8" S08E 31 lks.
This corner is recorded in the Burdell Twp. Book, pages 32 & 33 as 3" gas pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" iron rod 0.11 feet below road surface. Found 2" pipe 7" below road surface. Set Osceola County Monument 3" below road surface leaning to east with center over 2" pipe. Corner is 4' West of road centerline.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner E-8. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.
Gas line R/W marker S10E 107.95 feet.
10" W. Pine N25E 58.75 feet.
4": Elm N55W 24.30 feet.
30" W. Pine S85W 146.35 feet. OBT.
Also found dead 9" W. Pine N40E 38 feet.

Nancy Campbell
94 JUL -7 PM 3:25
OSCEOLA COUNTY REGISTER OF DEEDS

Signed by Matthew McClung Date June 8, 1994
Surveyor's Michigan License No. 13037