

**SURVEY &  
REMONUMENTATION**

DEC 16 1996

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>10W</u>	<u>F-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

OSCEOLA COUNTY  
REGISTER OF DEEDS  
96 NOV -7 AM 11:50  
APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County  
*Matthew McClung*  
10 Oct 1996  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Matthew McClung in a field survey on 09-14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

The original corner was set by deputy surveyor Sylvester Sibley on 7 July 1838. Set wood post 39.92 chains from East.  
Section Corner is 8" Cedar  
I have shown 1 LCRC; Liber 1, page 187

I have shown 2 PA 132: Liber 305, Page 333; Liber 352, Page 417.

Burdell Township Book; Pages 8,9,10 and 11 also, pages 32,33,34 and 35.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found eye bolt accompanied by 2 rods 3' South of centerline of East and West road, 5" below surface. Removed eye bolt and rods and placed Osceola County Monument in position of eye bolt 6" below surface. Eye bolt beneath Brass Cap on Se side. Corner is 6' East of fence row South.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner F-7. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
16" W. Pine W/nail S8W 49.85 feet.  
34" Maple South 20.25 feet 19.8 feet to nail O.B.T.  
30" Maple S58W 37.60 feet 37.0 to nail O.B.T.  
Power Pole North 66.55 feet.

Signed by *Matthew McClung*  
Surveyor's Michigan License No. 13037

Date Sept. 14, 1996

