

**SURVEY & REMONUMENTATION**

NOV 16 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola

(County)

Located In:

Corner Code #

1. Public Land Survey

T20NR 7W

B-8

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Matthew McClung in a field survey on 6. 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Act. 132, Liber 550, pages 352 & 353.

Corner falls in river

Witness corner on N & S 1/4 line 14.26' north of Center.

Witness corner on E & W 1/4 line 157.65' west of Center.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The position for this corner was determined by intersecting the one Quarter lines of Section 19. The corner falls in the river, and I have listed witness irons.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner B-8. No corner exists, falls in river.

Witness iron on North and South one quarter line, 14.26 feet North of Corner.

Witness iron on East and West one Quarter Line, 157.65 feet West of corner.

Signed by Matthew McClung  
Surveyor's Michigan License No. 13037

Date 15 Oct 98

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*Matthew McClung*  
25 JUN 98

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

*Shirley Campbell*  
98 OCT 15 PM 4:44  
OSCEOLA COUNTY  
REGISTER OF DEEDS

