

SURVEY &  
REMONUMENTATION

NOV 16 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>20</u> R <u>7</u> W	<u>C-8</u>
	T <u>  </u> R <u>  </u>	<u>  </u>
	T <u>  </u> R <u>  </u>	<u>  </u>
	T <u>  </u> R <u>  </u>	<u>  </u>
2. Property Controlling in Section	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
3. Miscellaneous Property in Sec.	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>
	S <u>  </u> T <u>  </u> R <u>  </u>	<u>  </u>

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*Matthew McClung*  
2 July 98

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Matthew McClung in a field survey on 6, 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

The original corner was set by deputy surveyor Francis Coleman Sept. 27, 1856. Set Post 39.68 1/2 chains from South.  
Beech 9" N49E 20 lks.  
Hemlock 8" S36W 45 lks

From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Excavated to 10" Found Osceola County monument. Excavated to 14" and found wood stake. Excavated to 18" and found tile. Corner is in centerline of North and South Road and in fence to West. Corner is in center of



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C-8. Is a Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
14" Maple N20W 53.6 feet. O.B.T.  
12" Beech N60E 29.5 feet. O.B.T.  
30" Maple East 30.25 feet. O.B.T.  
12" Maple S50W 35.3 feet.

Signed by *Matthew McClung*  
Surveyor's Michigan License No. 13037

Date 15 Oct 98

OSCEOLA COUNTY  
REGISTER OF DEEDS

98 OCT 15 PM 4:45

*Nancy Crawford*

SURVEY &  
REMONUMENTATION

NOV 16 1998

SECTION

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been entered in the County Surveyors records.

Marion Township Book  
Pages 10 Front Pages  
1/4 Cor 19 & 20 Tile  
Post N86W 30'  
Maple S87-1/2E 29.7'

Survey 132 Page 81  
Brass Cap  
28" Maple S88E 29.90'  
16" Maple N30W 54.45'  
10" Maple S40W 48.53'

Act 74 Liber 3, Page 46  
Brass Cap Monument  
16" Maple N30W 54.15'  
28" Maple S88E 29.9'  
10" Maple S40W 48.53'  
12" Beech N60E 29.40'