

DEC 06 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Osceola</u> <small>(County)</small>	Located In:	Corner Code #
	20N 7W	K-13
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

*Matthew M. McClung* COUNTY REP  
12 NOV 93

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Matthew McClung, in a field survey on November 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
The survey corner was set by deputy surveyor John Hodgson 4th quarter 1937. Set Wood post 80 chains from East.  
Pine 12" N88E 36 lks.  
Pine 9" N18W 8 lks.  
From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found 1/2" bar with cap No.30105 (H.C.W.-LLS) at road surface. Found 1/2" rod 1' below road surface, and 3" tile and cinders at 1'5" below road surface. Set Osceola County Monument 7" below road surface, and reset I & C on southwest side of monument.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Corner K-13. Osceola County Monument, which is a 3" brass cap mounted on a 1" pipe 18" in length.  
10" Cedar fence Post N08W 35.20 feet.  
Road sign post S38E 37.48 feet.  
Power Pole S20W 90.83 feet.  
5" Cherry (nail) N35W 37.40 feet.

Signed by Matthew M. McClung Date November 9, 1993  
Surveyor's Michigan License No. 13037

OSCEOLA COUNTY  
REGISTER OF DEEDS

93 NOV 16 PH 2: 35

*Nancy Crawford*

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been recorded in the County records.

A note in my records shows the corner as: iron, no witness.

There is a PA. 74 form recorded by Wilcox.