

SURVEY & REMONUMENTATION

NOV 16 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Osceola
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--|------------|
| 1. Public Land Survey | T <u>20</u> NR <u>8</u> W | D-2 |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

APPROVED LAND CORNER
P.A. 345 OF 1990
Osceola County
Matthew McClung
2 July 98
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung in a field survey on 6 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			•	4			3			2		1
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Act 132 Liber 418, Pages 19 & 20
No Witnesses
Highland Township Book Pages 52 & 53
Plow pt.

Act 74 Liber 2, Page 212
Fd. 1" Steel Bar
12" Apple N02W 69.15 ft.
Center of Maple Clump S75W
145.90'

OSCEOLA COUNTY
State of Michigan
Received For Record
Oct. 15, 1998 @ 4:45 P.M.
NANCY CRAWFORD
Register of Deeds

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Excavated to 7" and found 1" steel rod. Removed rod and excavated to 24" and found Plow Point. Placed Osceola County Monument in position of Rod 6" Below surface. Corner is 3 feet North of centerline and East and West Road and in fence row to North and South. As shown in Highland Township book, corner was set by intersecting the the One Quarter lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner D-2. Osceola County Monument, which is a 3" brass cap monument on 1" pipe 18" in length.
4" R. Pine S60E 89.2 feet.
12" Apple N03W 69.55 feet. O.B.T.
6" Elm N68E 58.05 feet.
3" Cherry S50W 109.35 feet.



Signed by *Matthew McClung*
Surveyor's Michigan License No. 13037

Date 15 Oct 98