

SURVEY & REMONUMENTATION


DEC 13 2000

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

For corners in		Located in:	Corner Code#
Osceola			
1. Public Land Survey		T 20 N R 8 W	E-11
		T R	
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	
4. Lot No. _____ Recorded Plat _____			
5. Private Claims _____			


OSCEOLA COUNTY REGISTER OF DEEDS
00 NOV - 2 PM 4: 11
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 13, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

E-11 - Section corner common to Sections 28, 29, 32 & 33, T20N, R8W.

- A. Description of original monument and accessories and/or subsequent restoration:**
- | | | |
|--|--|--|
| <p>1838 - S. Sibley, G.L.O.
 #1 - 10" Hemlock N14°W 11 Links
 #2 - 8" Beech S47°E 4 Links</p> <p>1891 - L. June, Surveyor
 Remonumented T20N, R8W with 3" Clay Tiles.
 "O.B.T'S Found".</p> <p>1905 - Co. Sur. Twp. Book
 #3- Fe. Post N35°E 54 Links
 #4 - Beech S9½°E 65 Links
 #5 - Distance East = 2578'
 #6 - Distance North = 2625.5'</p> | <p>Undated from Co. Sur. Twp. Book
 2" Well Point
 #7 - Rock Highpoint N.W 75'
 #8 - 6" Maple N.E. 63.5'
 #9 - Distance West = 2626'
 #10 - Distance South = 2633.8'</p> <p>1918 - F. McClung, Co. Sur.
 "Tile"
 #3 - Post N38 ½°E 36 ½'
 #11 - Post N30 ½°E 20 ½'
 #9 - Distance West = 2626'
 #10 - Distance South = 2633.8'</p> | <p>1974 - E. Benkert, LS 1237
 Survey recorded L. 311, Pg. 560.
 #12 - P. Pole N45°E 41.5'
 #13 - 10" Elm N38°W 45.5'
 #5 - Distance East = 2611.0'</p> <p>1979 - L. Cavanagh, LS 17614
 L.C.R.C. - Liber 02, Pg. 145.
 Survey recorded L. 311, Pg. 650.
 ½" Bar over well point.
 #7 - Rock High Point N34°W 75.0'
 #8 - 12" Maple N29°E 63.5'
 #14 - 6" Poplar S33°E 47.1'
 #15 - Road Sign Post S46°W 46.6'</p> |
|--|--|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 I found a 1" pipe with an Osceola County Brass Cap at the intersection of roads North, South, East and West. I excavated with a backhoe and at a depth of 4 feet I found an old pine stake surrounded with broken crockery. It was within a foot of where the 1" pipe was found. I also excavated the entire area looking for the clay tile but did not find it. I believe road construction destroyed the tile. I accepted the position of the 1" Pipe.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Measured 2610.04' #6 Measured 2647.5', #7 Found in good condition, #8 Gone, #9 Measured 2624.60' #10 Measured 2632.85', #11 Gone, #12 Gone, #13 Gone, #14 Gone, #15 Gone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I replaced the old 1" pipe with a 1" x 18" Pipe with Osceola County Remon Cap, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 10" W. Pine N61°E 65.08' (60d spike E. side)
- 14" Spruce S32°W 70.23' (center)
- Highest Point on Rock N36°W 75.09' #7
- P. Pole N34°W 103.85' (P.K. Nail West side)
- 4" W. Pine N34°E 79.68' (60d spike W. side)

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Osceola County
R.L.W.
10-31-2000



Signed by Robert L. Wetherell
 Surveyor's Michigan License No. 24624

Date November 1, 2000

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 ADAPTED FOR WORD PROCESSING JANUARY, 1999