

FEB 24 2000

**LAND CORNER RECORDATION CERTIFICATE**  
FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

For corners in Osceola	Located in:	Corner Code#
1. Public Land Survey	T 20N R 8W	J-1
	T R	
	T R	
	T R	
2. Property Controlling s in Section	T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____ Recorded Plat		
5. Private Claims		

OSCEOLA COUNTY  
REGISTER OF DEEDS  
99 NOV 19 PM 12: 09  
*Harvey Campbell*

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on September 30 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: ONLY ONE CORNER MAY BE RECORDED ON THIS CERTIFICATE.**

N ¼ Corner of Section 2, T20N,R8W

**A. Description of original monument and accessories and/or subsequent restoration:**

<u>1891- L. June</u> "Set by Measurement" Set 3 Clay Tile	<u>1923-1956 F. McClung</u> Highland Twp Book Pages 84 & 85 #3- Maple NE 27.1' #4- Maple SW 27.7' Dist. West 2649.50' Dist East 2660.10'	<u>1998-M. McClung 13037</u> Unrecorded Survey Fd. Iron & Cap 13037 and Iron 42" below surface Set Osceola County Monument #5- P. Pole (Center) N18W 76.45' #6- 6" Elm S12E 25.83' #7- 12" Butternut S65W 59.48' #8- Top Center Tele. Ped. S82W 128.80' Dist. East 2658.87' Dist. West 2648.88'
---	--	--

**B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:**

Found Osceola County Monument +/- 1' South of the C/L of East and West Road and in line with fence South.

Condition of the accessories are as follow: #3 Gone, #4 Gone, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition and #8 Found in good condition.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**


I accept the Osceola County Monument (1 ½" pipe with an Osceola County Remon Cap) as a substantial marker of the corner and is accepted as a careful and faithful reestablishment of the position of the original corner.

- P. Pole N18W 76.450'(Center) - #5
- 6" Elm S12E 25.9'(Nail on W. side) - #6
- 12" Butternut S65W 59.15'(Nail on SE side) - #7
- Top Center Tele. Ped. S82W 128.80' - #8

Signed by Robert L. Wetherell

Date Nov. 9, 1999

Surveyor's Michigan License No. 24624



APPROVED LAND CORNER  
P.A. 345 OF 1990  
Osceola County

10-21-99  
R L W.