

**SURVEY &
REMONUMENTATION**

JUN 9 9 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Osceola</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>20N</u> R <u>8W</u>	<u>L-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

APPROVED LAND CORNER
P.A. 848 OF 1990
Osceola County

Matthew McClung
24 April 1997

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Matthew McClung, in a field survey on Apr 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
The original corner was set by deputy surveyor Sylvester Sibley July 7, 1938. Set wood post 40.05 chains from the East. With no calls to river.
Hemlock 14" S71E 54 lks.
Hemlock 10" N18W 9 lks.
From 1891 to 1904 approximately, Osceola County had a remonumentation program, in which surveyors Temple and Trumbull, did the work. For the most part, a 3" glazed tile filled with cinders from a forge, were placed at each government set corner in the township. There were supposed to be 3 tile per corner, placed atop of each other, (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 5/8" iron rebar in monument box, In centerline of East and West road. Placed Osceola County Monument over 5/8" rebar in monument box. Distance to West is 2,655.98 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner L-9. Osceola County Monument, which is a 3" brass cap mounted 1" pipe 18" in length.
Guard Rail Joints attached to 6" I-Beam Post N54W 33.60 feet.
Guard Rail Joints attached to 6" I-Beam Post N14E 27.15 feet.
Guard Rail Joints attached to 6" I-Beam Post S8W 23.12 feet.
Guard Rail Joints attached to 6" I-Beam Post S40W 34.35 feet.
Plat Monument S01 degrees 51' 36" W 59.85 feet.



Signed by *Matthew McClung* Date April 21, 1997
Surveyor's Michigan License No. 13037

thereby making the corner 4 feet long. Sometimes a solid tile, with a cross in the top was used, and sometimes a 1/2" iron bars were added to the tile. Notes of the work were kept in ledgers, and given to the townships, and 5 of the townships have been entered in the County Surveyors records.

Act 74:
Liber 1, page 17
Dated: 15 June 1971
Short bolt in bituminous concrete on bridge
Uppermost NE corner of bridge orifice SE 45.5'
Uppermost SE Corner of bridge orifice NE 46.3'

Act 132:
Liber 321 Page 40
Dated 15 May 1975
No witnesses

Liber 289, Page 230
Dated 15 June 1971
No witnesses
Shows E1/2 of Sec. 24-25 to be 2650.6'

Marye Campbell
OSCEOLA COUNTY
REGISTER OF DEEDS
97 APR 30 PM 12:33

Highland Township Book:
Pages 88 & 89
Dated: 1956
W 1/2 North line Section 25 = 2655.7 feet and E 1/2 North line of Sec 25 = 2651.3'.

Pages 56 and 57
Dated prior to 1926
Shows the W 1/2 North line to be 2658.'

SURVEY &
REMONUMENTATION

JUN 09 1997

COMMISSION